BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Detailed Estimate for Cleaning of burial ground and providing water tank at Kattigenahalli Burial ground in ward No. 05

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	4800.00	KSRRB 200-clearing and grubbing road landKSRRB 200-8 : Cleaning and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and tress of girth upto 300mm by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials within a lead of 100 meters from road boundary, labour charges complete as per specifications.	Sqm	10.80	Rupees Ten and Eighty Paise Only
2	395.10	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 141/ Item No. 19.1/ PWD SR 2016-17	Cum	140.40	Rupees One Hundred Forty and Forty Paise Only
3	3.38	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in **ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from	Cum	322.92	Rupees Three Hundred Twenty Two and Ninety Two Paise Only
4	0.68	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2018-19	**Cum**	5510.16	Rupees Five Thousand Five Hundred Ten and Sixteen Paise Only
5	4.50	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2018-19	**Sqm**	5921.64	Rupees Five Thousand Nine Hundred Twenty One and Sixty Four Paise Only
6	0.68	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2018-19	**Cum**	6111.72	Rupees Six Thousand One Hundred Eleven and Seventy Two Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	6.00	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2018-19	Sqm	104.76	Rupees One Hundred Four and Seventy Six Paise Only
8	2	KSRRB M2900-2.1: Laying reinforced cement concrete pipe NP4 / prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets complete as per specifications, MORTH Specification No 2900 A.1200mm dia , No. 257 Item No. 34.2 PWD SR 2018-19	No.	10956.60	Rupees Ten Thousand Nine Hundred Fifty Six and Sixty Paise Only
9	2	Erection of RCC Hume Piepe Pump House/Cistern on size stone masory platform including transportaion charges and handling with all necessary tools and plants complete as directed by the Engineer in charges of works Page No. 20, I No. 3.17 PRED SR 2012-13	Each	1220.00	Rupees One Thousand Two Hundred Twenty Only
10	2	Labour charges for giving 50MM dia G.I Pipe end connection from rising main to cistern including cutting thereding conveying laying abnd jointing etc., complete inclusive of fixing 4 Nos. of 20mm dia, G.I Pipes with taps to the cistern. Page No. 19, I No. 3.13 PRED SR 2012-13	Each	1388.00	Rupees One Thousand Three Hundred Eighty Eight Only
11	8	Providing and Constructing stand post of size 1.22mX1.22m for public foundation with RCC post of size 1.22mS0.38mX0.10m with top rounded and RCC kerb slabs of size 1.22mX0.30mX0.05m in CC 1:2:4 proportion with 12mm size granite, trap or basalt jelly with nominal reinforcement as per design, plastring with CM 1:4 20mm thick to the exposed faces, with pot rest slab of size0.45mX0.30mX0.20m in CC 1:2:4 proportion with central dip and CC platform 1:2:4 proportion 10cm thick and smooth finishing with CM 1:3 to exposed faces with necessary from work, centring, mixing curing as per specifications including cost of steel and necessary earthwork excavation and disposing of the excavated earth as directed with all leads and lifts ect. **Page No. 20, I No. 3.16 PRED SR 2012-13**	**Each**	2707.00	Rupees Two Thousand Seven Hundred Seven Only
12	65.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19)	Mtr	394.32	Rupees Three Hundred Ninety Four and Thirty Two Paise Only
13	35.10	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, No. 6/ Item No. 2.11/ PWD SR 2013-14	Cum	60.48	Rupees Sixty and Forty Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
14	2	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13, Page No. 100 Item No. 13.55 / PWD SR 2018-19	Nos	1436.40	Rupees One Thousand Four Hundred Thirty Six and Forty Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))